





CITY OF LAS VEGAS		Public Works Department City Engineering Division Offsite Inspection and Testing Section			Procedure No.: PWOIT – MT 107
		Procedure: Offsite Grading Report			Page 1 of 11
Revision Number	Prepared By	Reviewed By	Approved By	Date Issued	
0	GGJ	GGJ	BM	GGJ	
Date	1-17-96	5-12-96	9-3-96	9-3-96	
1	GGJ	GGJ	DWM	GGJ	
Date	6-7-01	9-17-01	9-17-01	9-17-01	
2	GGJ	GGJ	DWM	GGJ	
Date	3-15-02	9-18-02	10-8-02	10-12-02	
3	GGJ	GGJ	DWM	GGJ	
Date	6-19-03	6-25-03	7-1-03	7-1-03	
4	GGJ	GGJ	DWM	GGJ	
Date	8-11-04	8-24-04	8-30-04	8-30-04	
5	GGJ	GGJ	TEH	GGJ	
Date	3-10-05	5-24-05	6-6-05	6-6-05	
6	GGJ	GGJ	TEH	GGJ	
Date	8-29-05	11-29-05	11-29-05	11-29-05	
7	GGJ	GGJ	TEH	GGJ	
Date	5-17-06	3-8-07	3-8-07	3-8-07	
8	GGJ	GGJ	TEH	GGJ	
Date	7-16-08	9-24-08	10-13-08	10-13-08	
9					
Date	3-8-10	6-22-10	6-28-10	6-28-10	
Date					
Date					



LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

STEVE WOLFSON

LOIS TARKANIAN

STEVEN D. ROSS

RICKI Y. BARLOW

STAVROS S. ANTHONY

ELIZABETH N. FRETWELL
CITY MANAGER

PUBLIC WORKS DIRECTOR
JORGE CERVANTES
P.E., P.T.O.E.

**DEPARTMENT OF PUBLIC WORKS
CITY ENGINEER DIVISION
Offsite Inspection and Testing Section**

**City of Las Vegas
Offsite Grading Report
Procedure No. PWOIT-MT 107 Revision 9**

The italicized and underlined sections of this policy note Revision 9 changes.

1. PURPOSE.

1.1. This policy establishes the guidelines by which the City of Las Vegas CLV will review and approve an Offsite Grading Report for public / private offsite improvement areas. The public offsite area is defined from the back of the sidewalk to back of sidewalk. The private offsite area is defined from the back of curb to back of curb on private streets. The grading defined limit is to the top of the subgrade of sidewalk, curb / gutter, utility trenches, and street. The CLV Quality Assurance (QA) Program is limited to monitoring of grading operations to periodic density testing of finish subgrade, and confirmation density testing of Aggregate Base materials, for public off-site improvements. All required construction phase reports should have been submitted and approved prior to the submittal of the Offsite Grading Report.

1.2. A Final Offsite Grading Report is required to be submitted for review and approval dependent upon the project Scope of Work.

NOTE 1: Quality Control (QC) subgrade density tests for public offsite areas including sidewalk and valley gutters; Bus Turn Out and Turn Lanes (not associated with new asphalt paving in the street area) are not required to be submitted in the formal "Offsite Grading Report". A copy of the "Field Density" test data sheet shall be given to the CLV Inspector for his review and approval prior to scheduling QA density tests. The requirements for the test data are the same as that for the Interim Subgrade Verification Reports.

2. REFERENCE CODES AND STANDARDS:

2.1. Associated CLV Procedures:

2.1.1. Procedures PWOIT MT 101 "Submittal of Reports".

2.1.2. PWOIT MT 102 "Type III Pipe Zone Backfill Material Report".

2.1.3. PWOIT MT 103 "Utility Trench Backfill Material Report".

2.1.4. PWOIT MT 104 "Trench Backfill Report".

2.1.5. PWOIT MT 105 "Pavement Section Design Verification Report".

2.1.6. PWOIT MT 106 'Native Soils In-Lieu of (NILO) Imported Subbase Aggregate Report".

2.2. Clark County Uniform Standard Specification:

2.2.1. Section 105, "Control of Work".

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TTY 702.386.9108
www.lasvegasnevada.gov

2.3. **Other:**

- 2.3.1. NRS 338.176, NAC 625.550, the most current ASTM, AASHTO, NDOT test procedures as indicated in the applicable sections of the Uniform Standard Specifications.

3. **STATEMENT OF POLICY:**

3.1. **Submittal:**

- 3.1.1. Submittal format shall be completed in accordance with the current CLV procedures and in compliance with the NRS 338.176 and NAC 625.550 statutes.
- 3.1.2. The project developer or their representative, the project Quality Control Company (QC) shall submit a transmittal letter and Subgrade Verification Report / Offsite Grading Report to the CLV for review and approval.
- 3.1.3. This shall be performed after the completion of the grading operations within the offsite public / private right-of-way, after all required construction phase reports (refer to Section 2.3 of this procedure) have been submitted and approved by the CLV, and prior to the placement of Type I or Type II Aggregate Base material or preparation of Native-in-lieu of ("NILO") Type I material. The "NILO" material is considered to be an Aggregate Base material.

3.2. **Types of Interim Subgrade Verification Reports:**

- 3.2.1. There are three (3) different types of Interim Subgrade Verification Reports. Each one is for a separate area / use. These different reports cannot be combined into one (1) report.

NOTE 2: The Interim Subgrade Verification Report procedure was implemented to reduce the time frame between the start of QC testing and the QA acceptance of an area for placement of Aggregate Base materials.

NOTE 3: There will not be a Final Subgrade Verification Report

3.2.1.1. Interim Subgrade Verification Report – Curb and Gutter ***ONLY:***

- 3.2.1.1.1. This report may be used for the (QC) release of the curb and gutter subgrade / NILO area(s) only, prior to the placement of Type II Aggregate Base material or concrete for the curb and gutter.

- 3.2.1.1.2. The following conditions shall be met prior to testing the curb and gutter area and submitting this report.

1. The Type III Pipe Zone Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report (if applicable).
2. The *Utility Trench* Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report.
3. The curb and gutter are at the proper subgrade / NILO elevation.

3.2.1.2. Interim Subgrade Verification Report – Street **ONLY**:

3.2.1.2.1. This report may be used for the (QC) release of the street subgrade area(s) only, prior to the placement of Type II Aggregate Base material in the street. This report shall include any test information regarding structural fill placed in the area(s) to be accepted.

3.2.1.2.2. The following conditions shall be met prior to testing the street area and submitting this report.

1. The Type III Pipe Zone Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report (if applicable).
2. The Utility Trench Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report.
3. The Trench Backfill Report has been submitted and approved by the CLV for the area(s) in the report.
4. The Pavement Section Design Verification Report has been submitted to the CLV and approved for the area(s) in the report.
5. The Interim Curb and Gutter – ONLY Report has been submitted to the CLV and approved for the area(s) in the report.
6. The street Subgrade is at the proper elevation.

3.2.1.3. Interim Subgrade Verification Report – Curb / Gutter **and** Street.

3.2.1.3.1. This report may be used for the (QC) release of the same area / limits of curb / gutter subgrade / NILO area(s) and street subgrade area(s) prior to the placement of Type II Aggregate Base material. This report shall include any test information regarding structural fill placed in the area(s) to be accepted.

3.2.1.3.2. The following conditions shall be met prior to testing the curb/gutter and street area and submitting this report.

1. The Type III Pipe Zone Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report (if applicable).
2. The Utility Trench Backfill Material Report has been submitted and approved by the CLV for the area(s) in the report.
3. The Trench Backfill Report has been submitted and approved by the CLV for the area(s) in the report.
4. The Pavement Section Design Verification Report has been submitted to the CLV and approved for the area(s) in the report.
5. The curb and gutter are at the proper subgrade / NILO elevation.
6. The street subgrade is at the proper elevation.

3.2.2. Interim Subgrade Verification QC Testing:

- 3.2.2.1. The QC test area(s) (outline of gauge) shall be painted where the test was performed.
- 3.2.2.2. Any subsequent compaction effort / rework on the area(s) identified in the Interim Subgrade Verification Reports, after the QC tests are performed, will void the report.
- 3.2.2.3. If the test area(s) are not identified with paint or any of the required information is not included in the interim reports and attachments, the QA testing will not be performed and the report rejected.

4.0 **REPORTS:**

4.1 **General Requirements for Report Content:**

- 4.1.1 The report shall include, at a minimum, the following information:
 - 4.1.1.1 Revised reports shall include the date of the report being superseded, as well as the current revision date.
 - 4.1.1.2 Project / Permit Name (per Off-site Construction Permit Hard Card)
 - 4.1.1.3 Project / Permit Number (per Off-site Construction Permit Hard Card)
 - 4.1.1.4 Project / Permit Plan Number (per Off-site Construction Permit Hard Card)
 - 4.1.1.5 *Submittal and approval of the required Construction Phase Reports as noted in the Scope of Work. These* referenced reports shall be identified by the accepted QC report issue date and CLV acceptance letter date.
 - 4.1.1.6 The report must be prepared by, or under the direction of a Professional Engineer registered in the State of Nevada. The report shall be signed and stamped by the responsible engineer.

NOTE 4: The same curb / gutter and street areas must be approved at the same time in Offsite Grading Reports (except as noted in Interim Subgrade Verification Reports).

- 4.1.1.7 Use the appropriate approved project Plan and Profile sheets to determine the specific location for the area being submitted for review and acceptance **for this report**. The locations shall be noted in the text of the report in a similar format as shown below:

Table 1

<i>Street Name</i>	<i>Area of Acceptance</i>		<i>Station Number</i>	<i>to</i>	<i>Station Number</i>
	<i>C / G</i>	<i>STR</i>			

NOTE 5: If street names are revised after a construction phase report has been submitted to the CLV and approved by the CLV, subsequent construction phase reports shall reference the original street name as well as the revised street name.

- 4.1.1.8 A statement verifying the over excavation was performed per the Geotechnical Engineer recommendations (if over excavation was required by Geotechnical Investigation Report).

NOTE 6: The test data for the over excavated area shall have been included with the Pavement Section Verification Report

- 4.1.1.9 The report shall contain a statement that verifies that the grading and earthwork complies with the requirements and recommendations of the project geotechnical report, project plans, specifications, and current CLV policies and procedures
- 4.1.1.10 Sieve Analysis.
- 4.1.1.11 Plastic Index.
- 4.1.1.12 Proctor information per current AASHTO T180 procedure and include a curve for each material type
- 4.1.1.13 Plot plan with sample locations identified and areas indicated that are represented by the sample. The accepted area shall be in such a manner that the area is identifiable on "Xerox" copies.
- 4.1.1.14 If testing is provided by another laboratory, that data shall be stamped by the responsible engineer and included in the report.

4.2 Additional Requirements for Interim Subgrade Verification Report:

- 4.2.1 Interim Subgrade Verification Report Submittal:
 - 4.2.1.1 The report shall be submitted to the CLV for review / approvals within two (2) workdays of the date the first tests were performed; otherwise the test data cannot be used for the Interim Subgrade Verification Report.
 - 4.2.1.2 The QC Company will verify that all pertinent construction phase reports have been accepted by the CLV prior to submittal of the report (refer to section 3.2)
 - 4.2.1.3 The report title shall be **Subgrade Verification Report** – (one of the following):
 - 4.2.1.3.1 Curb and Gutter - **ONLY** or
 - 4.2.1.3.2 Street - **ONLY** or
 - 4.2.1.3.3 Curb / Gutter and Street

4.2.1.4 The specific location of the area(s) being accepted along with the minimum information as shown on Attachment No. 1 shall be included in the text of the report in a similar format as shown in **Attachment No. 1**

4.2.1.5 A statement verifying the over excavation was performed per the Geotechnical Engineer recommendations (if over excavation was required by Geotechnical Investigation Report). See attachment No. 1

NOTE 7: The test data for the over excavated area shall have been included with the Pavement Section Verification Report

4.2.1.6 Copies of the hand written "Field Test Data" sheets will contain the following minimum information:

1. Test number.
2. Test date
3. Test location (per project grading plan)
4. Test station number (per project grading plan)
5. Type of test (i.e. curb/gutter subgrade/NILO etc)
6. Test elevation (per project plan)
7. Depth of fill
8. Dry Density
9. Moisture Content
10. Gauge Serial Number
11. Gauge density / moisture count for each test
12. Direct transmission depth of test (i.e. 6", 8", or 10" etc)
13. Maximum Dry Density (MDD)
14. Optimum Moisture for MDD
15. Test result
16. Test requirement
17. Pass / Fail

4.3 Additional Requirements for Interim Offsite Grading Reports:

4.3.1 Interim (partial area release) reports for specific areas of work (i.e., interior/exterior curb / gutter and/or street areas and / or portion of those areas) are acceptable; however they shall be referenced in the Final Offsite Grading Report.

4.3.2 The report title shall be **Interim Offsite Grading Report**.

4.3.3 Referenced CLV approved reports.

4.3.3.1 Interim / Final Trench Backfill Report

4.3.3.2 Interim / Final Pavement Section Design Verification Report

4.3.3.3 Interim Subgrade Verification Report – Curb / Gutter ONLY

4.3.3.4 Interim Subgrade Verification Report – Street ONLY

4.3.3.5 Interim Subgrade Verification Report – Curb / Gutter and Street

- 4.3.4 The subgrade density tests shall have been performed within sixty (60) calendar days of the report submittal to the City of Las Vegas for review and approval.
- 4.3.5 Test data shall be typed and contain the following minimum information:
1. Test number.
 2. Test date
 3. Test location (per project grading plan)
 4. Test station number (per project grading plan)
 5. Type of test (i.e. curb/gutter subgrade/NILO etc)
 6. Test elevation (per project plan)
 7. Depth of fill
 8. Dry Density
 9. Moisture Content
 10. Gauge Serial Number
 11. Gauge density / moisture count for each test
 12. Direct transmission depth of test (i.e. 6", 8", or 10" etc)
 13. Maximum Dry Density (MDD)
 14. Optimum Moisture for MDD
 15. Test result
 16. Test requirement
 17. Pass / Fail
- 4.3.6 Laboratory test results (i.e., swell, solubility tests, and gradation tests) qualifying the use of the soils / aggregates in accordance with the Clark County Uniform Standard Specifications, project Geotechnical Investigation recommendations, and project specifications

4.4 Additional Requirements for Final Offsite Grading Report:

- 4.4.1 This is the **last report**, for project, if Interim Reports were issued. It is the **only report** if Interim Reports were not issued.
- 4.4.2 The report title shall be "**Final Offsite Grading Report**".
- 4.4.3 Referenced CLV approved reports.
- 4.4.3.1 Final Trench Backfill Report
- 4.4.3.2 Final Pavement Section Design Verification Report
- 4.4.3.3 Interim Subgrade Verification Report – Curb / Gutter ONLY
- 4.4.3.4 Interim Subgrade Verification Report – Street ONLY
- 4.4.3.5 Interim Subgrade Verification Report – Curb / Gutter and Street
- 4.4.3.6 Interim Offsite Grading Report
- 4.4.4 The subgrade density tests shall have been performed within sixty (60) calendar days of this reports submittal to the City of Las Vegas.

4.4.5 Report information / test data included with approved reports, per section 4.1.1.5, shall not be included with the Final Report

4.4.5.1 Test data shall be typed and contain the following minimum information:

1. Test number.
2. Test date
3. Test location (per project grading plan)
4. Test station number (per project grading plan)
5. Type of test (i.e. curb/gutter subgrade/NILO etc)
6. Test elevation (per project plan)
7. Depth of fill
8. Dry Density
9. Moisture Content
10. Gauge Serial Number
11. Gauge density / moisture count for each test
12. Direct transmission depth of test (i.e. 6", 8", or 10" etc)
13. Maximum Dry Density (MDD)
14. Optimum Moisture for MDD
15. Test result
16. Test requirement
17. Pass / Fail

4.4.6 Laboratory test results (i.e., swell, solubility tests, and gradation tests) qualifying the use of the soils / aggregates in accordance with the Clark County Uniform Standard Specifications, project Geotechnical Investigation recommendations, and project specifications

5 QUALITY CONTROL TESTING:

5.4 Density Testing:

5.4.1 The testing shall be performed by Quality Control Company AASHTO Accredited in the procedures being reported. The most current ASTM, AASHTO, NDOT test procedures shall be used. Testing requirements shall be from the applicable sections of the Uniform Standard Specifications and current CLV policies and procedures.

NOTE 8: The requirement for the AASHTO Accreditation is mandatory for all laboratories performing work submitted to the City of Las Vegas, Offsite Inspection and Testing, effective March 1, 2008. Laboratories that are not accredited in the test procedures being submitted shall contact the City of Las Vegas, Offsite Inspection and Testing prior to submitting the test information.

5.4.2 Testing determinations shall be made in lots, each lot represents the subgrade area ready for testing for each direction of travel (i.e., south bound and north bound areas) for full street construction. A lot shall be divided into sublots and tested to a frequency indicated in Table 2, and one (1) test minimum shall be made for each sublot. The Quality Control Company Engineer may require additional density tests, beyond the minimum number required, if they determine there is a need for additional testing. In this case, the additional tests are not required to be located by random number.

NOTE 9: Half street construction only requires lot / subplot determination for one direction of travel applied to the complete half street width.

- 5.4.3 The location of the field density tests shall be chosen on a random number basis. If requested by CLV, a summary of the information used to determine lot/ subplot descriptions shall be completed and shall be included with the submitted report.
- 5.4.4 Minimum density test probe depth shall be 8" on 12" compacted fill. The minimum probe depth shall be per the project Geotechnical Report on "cut" areas requiring scarification unless not specified; then the minimum probe depth for the density test shall be 8".

Table 2


Area	Test	Procedure	Frequency
Street	Field Density Test	AASHTO T310	1 / 5000 ft ² / lift ^{1,2}
Curb / Gutter	Field Density Test	AASHTO T310	1 / 250 Linear Feet / lift ¹
Sidewalk	Field Density Test	AASHTO T310	1 / 250 Linear Feet/ lift ¹

Lift ¹ = 12" Compacted Fill

Lift ² = lot / subplot is not to exceed 250 linear feet in length for half street construction

6 EFFECTIVE DATE AND APPROVALS:

EFFECTIVE DATE: July 1, 2010



Thomas Hayes, P.E.

City of Las Vegas

Land Development / Offsite Inspection and Testing Manager

6-28-10

Date



Gary G. Johnson

City of Las Vegas

Construction Testing Supervisor

6-28-10

Date

**Interim Subgrade Verification Report – Curb and Gutter ONLY or
Street ONLY or
Curb/Gutter and Street**

PROJECT NAME: _____

REPORT DATE: _____

PROJECT LOCATION: _____

CLV PROJECT / PERMIT NO. _____ CLV INSPECTOR: _____

CLV PROJECT PLAN NO. _____

DEVELOPER NAME: _____

QC COMPANY NAME: _____ QC PROJECT NO. _____

This report represents the following area(s):

Area(s) of Acceptance								
Street Name	Curb / Gutter			Street Subgrade		Station	to	Station
	“NILO”	Subgrade	Side N,S,E,W	Half Street	Full Street			

NOTE 13: If street names are revised after a construction phase report has been submitted to the CLV and approved by the CLV, subsequent construction phase reports shall reference the original street name as well the revised street name

Attached to this form are copies of associated Field Density tests representing the identified curb and gutter / street (specify which), NILO / subgrade (specify which) area(s).

Minimum density compaction requirement for the curb / gutter NILO / subgrade (specify which) is XX% and /or minimum density compaction requirement for street subgrade is XX%.

The Construction Phase reports required prior to this report submittal have been reviewed and accepted by the CLV.

Over excavation and structural fill placement of the offsite area has been completed in accordance with the Geotechnical Evaluation Report of record.

The above noted area(s), the curb and gutter / street area(s) (specify which), NILO Type 1 or subgrade area(s) (specify which) have been prepared in general accordance with the Geotechnical Evaluation Report of record, project plans and specifications, current CLV policies and procedures.

Prepared By _____

Affix Seal, Sign and Date _____